8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing a sandal koti at Shimoga.

Items of work	Per	Quantity
Earthwork excavation	C. yd.	1,106
Earthwork (filling, watering and tamping)	C. yd.	620
Concrete	C. ft.	9,845
Burnt stone in chunam with bond stones	C. ft.	21,634
Burnt stone in chunam archwork	C. ft.	38
Burnt brick in chunam	C. ft.	29,635
Do archwork	Do	156
Do pillars, complete	Each	6
Burnt stone slabs roughly dressed	S. ft.	722
Plastering with chunam and smoothing	Sqr.	400·78
White and colour-washing, two coats	Sqr.	400·78
Teakwood doors and windows with hinges, etc., complete	S. ft.	670
Teakwood ventilators with iron bars and glazed shutters	S. ft.	60
Do almirahs, complete	S. ft.	25
Do Borge board, complete and painting	S. ft.	70
Do eave board, complete and painting	S. ft.	14·2
Do gate, complete and painting	S. ft.	115
Do finials, complete and painting	Each	5
Chocolate painting	Sqr.	13·75
Wood oiling	Sqr.	7·25
Teakwood work wrought and put up	C. ft.	1540·89
Roofing with 1st class Mangalore tiles and teak reepers, etc., complete	Sqr.	196·16
Roofing glass tiles	Each	68
Flooring with Cuddappah slabs on 3" concrete bed and cement pointing	Sqr.	104·26
Concrete to floor of work-shed	C. ft.	351
Jambe-wood blocks setting and pointing with pitch	C. ft.	439
Roofing with galvanized iron sheets	Sqr.	22·80
Zinc sheets to valleys	S. ft.	226
Chunam borders	R. ft.	171
Ridge tiles set in mortar	R. ft.	676
Pointing with chunam	Sqr.	25·18
Preparing sham door	L. S.	Rs.
Clearing site and levelling ground	Do	...
Drainage tunnel and gravelling, etc.	Do	...
Ceiling with Mangalore tiles	Sqr.	111·94
Teakwood pillars with capitals and basses 12' high	Each	13
Teakwood pillars with capitals and base 10½' high	Each	13

F. A. STEELE,
Executive Engineer.

KADUR DISTRICT.

Notice dated 22nd February 1910.

It is hereby notified that the 3rd class travellers' bungalow at Ajjampur in the Tarikere Taluk will be closed to the public for about two months from the 1st of March 1910, as the same is under repairs.

S. CHAKRAPANI IYENGAR,
For *President, District Board.*

KOLAR DIVISION.

NOTICE.

1. A sum of Rs. (54-5-6) fifty-four, annas five and pies six, being arrears due to Venkatesaiya for restoring the Lakkasettihalli tank, is outstanding since June 1907, as per accounts of this office. If Venkatesaiya or his legal representative fails to claim the amount within three months from the date of the publication of this notice in the *Mysore Gazette,* it will be credited to Government and no claim will thereafter be entertained.

2. A sum of Rs. (4-4-6) four, annas four and pies six, being arrears due to Eeregauda for restoring the Jannapalli tank, Srinivaspur Taluk, is outstanding since June 1907, as per accounts of this office. If Eeregauda or his legal representative fails to claim the amount within three months from the date of the publication of this notice in the *Mysore Gazette,* it will be credited to the Government and no claim will thereafter be entertained.

B. B. GARUDACHARYA,
Executive Engineer.